



INTERNATIONAL CONSTRUCTION CONSORTIUM (PVT) LTD

PRE-CAST PRODUCTION

PRE-STRESSED, PRE-CAST CONCRETE
BRIDGE BEAMS & BRIDGE COMPONENT

DATA
SHEET



RDA
STANDARD

BRIDGE BEAMS
AND COMPONENT

CUSTOMIZED
DESIGN

BRIDGE
HANDRAILS



ICC PRECAST
FAST - QUALITY - INNOVATIVE



PRE-CAST PRODUCTION

PRE-STRESSED, PRE-CAST CONCRETE BRIDGE BEAMS & BRIDGE COMPONENT DATA SHEET

01. INTRODUCTION

International Construction Consortium (Pvt)Ltd is the leading of manufacturer of pre-stressed concrete bridge beams with precast bridge components in Sri Lanka. They are manufactured in accordance with DA standard specifications.

These products are manufactured by maintaining high quality controlling and quality assurance systems under engineering supervisions.

This publication provides the information necessary to specify pre stressed concrete bridge beams and bridge components for all of these applications.





PRE-CAST PRODUCTION

PRE-STRESSED, PRE-CAST CONCRETE BRIDGE BEAMS & BRIDGE COMPONENT DATA SHEET

02. GENERAL SPECIFICATIONS

STANDARD SPECIFICATION

RDA Standard
Project Standard

PRODUCTION SPECIFICATION

Dimensions: Refer the table
Concrete Strength(N/mm²): Grade 25/30/45/50

RAW MATERIAL SPECIFICATION



Cement: SLS 107 : 2015
Fine Aggregate: BS 882 - 1992
Coarse Aggregate: BS 882 - 1992
Reinforcement Steel : SLS 375 : 2009
(Mild steel)
Reinforcement Steel : BS 5896/2
(HTS-Strand)
Water : BS 3148 - 1980

03. PRODUCTION RANGE

LENGTH (MM)	RDA DRAWING NO.	
7010	T/B/030	Old Design
9500	T/B/507	New Design
11500	T/B/506	New Design
13500	T/B/505	New Design
14500	T/B/503 A	New Design
15500	T/B/502 A	New Design
16500	T/B/501 A	New Design
17500	T/B/515	New Design
19000	T/B/508 Rev 1	New Design

*Up Right unit
*Hand Rails
*Couplers
*Bridge kerb

04. BEAM SECTION DETAILS - INVERTED T BEAM



PRE-STRESSED, PRE-CAST CONCRETE BRIDGE BEAMS & BRIDGE COMPONENT DATA SHEET




PRE-CAST PRODUCTION



PRE-STRESSED, PRE-CAST CONCRETE BRIDGE BEAMS
& BRIDGE COMPONENT DATA SHEET

06. PRODUCT DETAILS-BRIDGE COMPONENTS

Up Right unit



Bridge Kerb








PRE-CAST PRODUCTION

PRE-STRESSED, PRE-CAST CONCRETE BRIDGE BEAMS
& BRIDGE COMPONENT DATA SHEET

Hand Rail & Coupler



Guard stone





PRE-CAST PRODUCTION

PRE-STRESSED, PRE-CAST CONCRETE BRIDGE BEAMS & BRIDGE COMPONENT DATA SHEET

07. HANDLING AND TRANSPORTATION

Precast bridge beams are transported after 28 days concrete cube strength is achieved.

While the transportation of beams, They should be well tied and recommended maximum height of beam stack is 1500mm. (fig. 01)




Fig.01 - Correct loading method for transportation.

Stacking should be always on even and firm ground surface.

"h" should be decided by the site conditions such as ground bearing capacity, availability of stacking areas.

"y" should be in accordance with relevant RDA beam drawing.

Put the support wedges vertically in line to avoid possible cracks.(table. 01)




Fig.02 - Correct method for stacking.




Fig.03 - Correct method for stacking.



PRE-CAST PRODUCTION

PRE-STRESSED, PRE-CAST CONCRETE BRIDGE BEAMS
& BRIDGE COMPONENT DATA SHEET




When the lifting of beam, use the safety methods with suitable part and equipments. (crane, lifting belt/chain, lifting rods,etc.)

Always use the lifting hole for the handling of beam.

Do not stand under during the lifting or handling. always use the guiding rope for handling the product.

Any jerk should be avoided the during lifting and handling.





PRE-CAST PRODUCTION

PRE-STRESSED, PRE-CAST CONCRETE BRIDGE BEAMS & BRIDGE COMPONENT DATA SHEET

Product Item	Ave. Weight per \approx (kg)
Up Right unit	80.5
Hand Rails	31
Couplers (a pair)	4.7
Bridge kerb	86

All bridge component & road item are to be stacked on even and firm surface in careful manner.

08. HANDLING, STACKING AND TRANSPORTATION

While transportation of bridge components, they should be well tightened with ratchet belts and recommended maximum height of stack is 1200mm. See fig 04




Fig.04 - Correct loading method for transportation.

09. TESTING & INSPECTION

Material test report and mill report
Concrete crushing strength. (test cube strength)
Imposed load test record.

International Construction Consortium (Pvt) Ltd

Precast Yard, # 508/2, Off Madapatha Road, Piliyandala, Sri Lanka.

Tel: +94 11 261 9160-4 Fax: +94 11 261 9164

Email: precast@icc-construct.com Web : www.icc-construct.com

